

Le Gia Phuc Construction & Trading Co., Ltd

Add: 17 Street 49 - Tan Phong Ward, Dist rict.7, HCMC

Tel: 84-8-54336768, Fax: 84-8-54330939, Email: info@legiaphuc.com

Option 1 sheet pile driving around tank

ITEM	DESCRIPTION	Length	Wide	Heigh	QTY	UNIT	Unit price (USD/Unit)			Amount
		m	(unit Weight)				Material	Labor	Total	(USD)
1-1	SHORING / STEEL SHEET PILE SYSTEM									
1	Driving steel sheet pile type III S.P type III (60kg/m 9m lengh)	153.00	60.00	9.00	82,620.00	kg			0.22	18,176.40
2	Install waller & strut	93.50	93.00	1.00	8,695.50	kg			0.41	3,565.16
3	Remove Waller & strut	93.50	93.00	1.00	8,695.50	kg			0.14	1,217.37
4	Extract steel sheet pile	153.00	60.00	9.00	82,620.00	kg			0.07	5,783.40
5	Mobilization				2.00	Trip			439.02	878.04
	1-1 SUB TOTAL OF SHORING / STEEL SHEET PILE SYSTEM									29,620.37

Option 2 sheet pile driving for only one side, along new-factory

ITEM	DESCRIPTION	Length	Wide	Heigh	eigh QTY UNIT Unit price (USD/Unit			Unit)	Amount	
		m	(unit Weight)				Material	Labor	Total	(USD)
1-1	SHORING / STEEL SHEET PILE SYSTEM									
1	Driving steel sheet pile type III S.P type III (60kg/m 9m lengh)	70.00	60.00	9.00	37,800.00	kg			0.22	8,316.00
2	Install waller & strut	31.00	93.00	1.00	2,883.00	kg			0.41	1,182.03
3	Remove Waller & strut	31.00	93.00	1.00	2,883.00	kg			0.14	403.62
4	Extract steel sheet pile	70.00	60.00	9.00	37,800.00	kg			0.07	2,646.00
5	Mobilization				2.00	Trip			439.02	878.04
	1-1 SUB TOTAL OF SHORING / STEEL SHEET PILE SYSTEM									13,425.69